No.	Items of work	Unit	Rate	Quantity	Rate to be tendered
	IV. Constructing a masonry waste weir 106 ft. long at the right flank with Crest at R. L. 51·00.		Rs. a. p.		
1	Earthwork excavation for foundation in hard soil	C.yd.	0 2 6	169	
2	Burnt stone jelly concrete in surki mortar ..	C.ft.	0 4 0	392	
3	Burnt size stone in surki mortar with bond stones..		0 4 6	1257	
4	Burnt stone slab 6″ thick dressed and fixed in mortar	S.ft.	0 4 6	452	
5	Providing joggles for joints of slabs	No.	0 8 0	13	
6	Cement pointing after racking joints	Sqr.	3 8 0	7·00	
7	Rough stone work new with jelly backing ..	C.yd.	1 8 0	98	
8	Approach and draft clearing to waste weir in hard soil for free flow of water and using the same for training bank at left in continuation of bund	C.yd.	0 3 0	425	

C. R. IYENGAR,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification dated 25th October 1939.

The attention of the public is drawn to the Notification calling for tenders for Improving the Second Class Travellers' Bungalow at Devarayandurga, published in page 2205, Part VI of the *Mysore Gazette*, dated 2nd November 1939.

2. The tenders will be received by the Executive Engineer up to 2 P.M. on 25th November 1939.

3. The earnest money required for the work is Rs. 255 which should be credited to the Treasury to '17 (*a*) P. W. Deposits' and the relative chellan enclosed.

Notification dated 2nd November 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M., on 2nd December 1939, for Restoring Mallenahalli Tank, Reg. No. 170, Turuvekere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1940.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. to 5 P.M.

3. Tender should be submitted on printed forms which may be obtained on payment of four annas for each form from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a duplicate chellan for Rs. 270 only credited to 17 (*a*) P. W. Deposits, as earnest money, and be superscribed "Tender for Restoring Mallenahalli Tank, Turuvekere Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per current schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for Restoring Mallenahalli Tank, Registered No. 170, Turuvekere Taluk.

Sl. No.	Description of work	Per	Rate	Quantity
	I. BUND.		Rs. a. p.	
1	Jungle clearing	L. S.		
2	Cutting longitudinal grips in old bund	Grade	2 0 0	34
3	Removing apron in the old weir cutting grips and trenches to receive fresh earth	L. S.		
4	Earthwork for closing the left weir with selected gravelly soil, watering and consolidation	C.yd.	0 6 0	485
5	Earthwork to bund with watering and consolidation, ordinary soil	,,	0 3 6	5,416
6	Excavating and conveying from draft and approach clearing of weir including watering and consolidation	,,	0 4 6	600
7	Earthwork to bund with watering and consolidation in gravelly soil	,,	0 4 0	2,560
8	Removing and resetting old stone work with new jelly	,,	0 12 0	527
9	New stone revetment	,,	1 8 0	352
10	Resetting old stone available from waste weir	,,	0 12 0	157
11	Turfing the slopes	S.yd.	0 0 9	8,417
12	Providing and fixing new grade stones	No.	2 0 0	37
13	Do B. M. stones	,,	2 8 0	2
14	Do Reg. No. stone	,,	3 0 0	1
15	Do Guage stone	,,	12 0 0	1
	II. SLUICE.			
1	Constructing sluice No. 1 at R.L. 43.50 with necessary repairs	L. S.		
2	Constructing sluice No. 2 at R.L. 43.50 in the same grade and blocking the existing one	,,		
	III. WASTE WEIR NO. 1 ON THE LEFT.-R.L. 50.00—125 FT. LONG.			
1	Earthwork excavation for draft and approach cutting including forming the training bund	C.yd.	0 3 6	197
2	Burnt stone jelly concrete in surki mortar	C.ft.	0 4 0	350
3	Size stone in surki mortar	,,	0 5 0	384
4	Providing and fixing burnt stone slabs 6″ thick dressed, etc.	S.ft.	0 7 0	503
5	Providing stone joggles with cement grouting	No.	0 10 0	20
6	Cement pointing deep with racking joints and clearing	Sqr.	4 0 0	4·50
7	Rough stone apron, new	C.yd.	1 8 0	55
	CONSTRUCTING WASTE WEIR NO. 2 ON THE RIGHT AT R.L. 50.00—45 FT. LONG.			
1	Earthwork excavation in stoney gravelly soil	C.yd.	0 4 0	17
2	Stone jelly concrete	C.ft.	0 4 0	150
3	Size stone in surki mortar	,,	0 5 0	205
4	Providing and fixing burnt stone slabs 6″ thick dressed	S.ft.	0 7 0	198
5	Providing stone joggles with cement grouting, etc.	No.	0 12 0	7
6	Pointing with cement mortar deep including racking and cleaning	Sqr.	4 0 0	2·00
7	Removing and resetting the damaged apron	C.yd.	0 12 0	11
8	New stone work	,,	1 8 0	15
9	Jelly filling below apron, etc.	L. S.		

P. RAJAGOPALAN,
Executive Engineer.